

## SCHEDULE B.

(The earnest money for this portion of work is Rs. 200 and the work should be completed within two months from the date of orders to start the work.)

| Sl. No. | Particulars                                                                                                                                                                                                                                    | Per   | Quantity  |
|---------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|-----------|
| 1       | Conveying, hoisting and fixing in position including necessary assembling, rivetting, etc., complete lattice girders 69 feet over all length.                                                                                                  | Each  | 2         |
| 2       | Conveying, hoisting and fixing in position including necessary assembling, rivetting, etc., complete R. S. I. purling, angle iron runners, etc.                                                                                                | Cwt.  | 125 Cwts. |
| 3       | Conveying, hoisting and fixing in position including necessary assembling, rivetting, etc., complete R. S. Trusses for 35 feet span including North light arrangements.                                                                        | Each  | 15        |
| 4       | Conveying, hoisting and fixing in position including necessary assembling, rivetting, etc., complete Crittal or other type of steel windows for North light including fixing Departmental glass panes with Contractor's putty, etc., complete. | S.ft. | 700 S.ft. |
| 5       | Conveying, hoisting and fixing in position 22 B. W. G. galvanised iron corrugated sheets including wind ties, ridging, etc., complete.                                                                                                         | Sqr.  | 8,600 "   |
| 6       | Conveying, hoisting and fixing in position 22 B. W. G. galvanised iron gutters 12" wide including fixing of brackets, soldering, etc., complete.                                                                                               | R.ft. | 218 R.ft. |
| 7       | Conveying, hoisting and fixing in position cast iron down water pipes 4" diameter including fixing supports in stone masonry.                                                                                                                  | "     | 138 "     |
| 8       | Removing galvanised iron corrugated roofing sheets and refixing the same in new positions.                                                                                                                                                     | Sqr.  | 500 S.ft. |
| 9       | Removing galvanised iron gutters and refixing the same in new position including fixing of brackets.                                                                                                                                           | R.ft. | 73 R.ft.  |
| 10      | Removing down water pipes and refixing the same in new position including fixing of supports in stone masonry.                                                                                                                                 | "     | 38 "      |
| 11      | Unloading materials from wagons and stacking including a lead of 300 feet.                                                                                                                                                                     | Ton   | 100 Tons. |

Specification for works will be according to Mauryat's Hand Book, Volume I.

R. N. MIRZA,  
Senior Executive Engineer.

## EXECUTIVE ENGINEER'S OFFICE, MYSORE RAILWAYS, MYSORE.

*Abstract Notification, dated 4th August 1933.*

The attention of the public is invited to the detailed notification calling for tenders for the Construction of Compound Wall in the Central Work Shop area, published on pages 956-957 of Part VI of the *Mysore Gazette*, dated 3rd August 1933.

R. N. MIRZA,  
Senior Executive Engineer.

## MISCELLANEOUS DEPARTMENTS

## DEPARTMENT OF AGRICULTURE, MYSORE STATE.

OFFICE OF THE MANAGER, GOVERNMENT EXPERIMENTAL FARM, HEBBAL.

*Abstract Notification, dated 24th July 1933.*

Sealed tenders will be received by the Manager, Government Experimental Farm, Hebbal up to 11 A.M. on Monday the 14th August 1933, for the supply of Cattle Feed and Miscellaneous Articles required for the year 1933-34 for this Farm.

For further particulars vide Notification No. 1111.